



El Dorado County Department of Transportation, District I Projects Fiscal Year 2024/2025

(All dates and costs for maintenance projects are estimated as of April 10, 2024)

Governors Area Road Repair and Surface Treatment

- **Description:** Includes the area west of El Dorado Hills Boulevard, north of Olsen Lane, south of Stephen Harris Park, and east of Kalithea Park. The project is a multi-year project. The first phases will concentrate on the preparation for the surface treatment. Phase one (1) will consist of roadside brushing of approximately 8.75 miles of roadway in the identified subdivisions and roadway. Brushing consists of removing hazardous trees and all low-hanging foliage and opening site distances as needed. Phase two (2) will consist of curb and gutter repairs and possible culvert repairs. All curbs and gutters will be evaluated and repaired if needed. At that time, all culverts will be inspected for life expectancy and replaced if needed. Phase three (3) will consist of repairing damaged asphalt in the 8.75 miles in the identified area, where needed, and possible ADA improvements. Phase four (4) will consist of a rubberized asphalt surface treatment and thermoplastic roadway markings.
 - Total Project Cost: \$1,750,000
 - Funding Source: Road Maintenance and Rehabilitation Act of 2017 (RMRA – SB1)
 - Project Start: November 2023
 - Estimated Project Completion: October 2024

Governors Area Phase 2 Road Repair and Surface Treatment

- **Description:** Includes Albert Circle, Cyprine Court, Gillett Drive, Hensley Circle, Mephram Court, Moonstone Circle, Plumley Court, Ridgeview Drive, Sapphire Way, Shelby Circle, Shelby Court, Suffolk Way, Tabari Court, Turquoise Way and Warren Lane in El Dorado Hills, California. The project is a multi-year project. The first phases will concentrate on the preparation for the surface treatment. Phase one (1) will consist of roadside brushing of approximately 5.5 miles of roadway in the identified subdivisions and roadway. Brushing consists of removing hazardous trees and all low-hanging foliage and opening up site distances as needed. Phase two (2) will consist of curb and gutter repairs and possible culvert repairs. All curbs and gutters will be evaluated and repaired if needed. At that time, all culverts will be inspected for life expectancy and replaced if needed. Phase three (3) will consist of repairing damaged asphalt in the 5.5 miles in the identified area, where needed. Phase four (4) will consist of a rubberized asphalt surface treatment and thermoplastic roadway markings.
 - Total Project Cost: \$1,500,000
 - Funding Source: Road Maintenance and Rehabilitation Act of 2017 (RMRA – SB1)
 - Project Start: November 2024
 - Estimated Project Completion: October 2025

El Dorado Hills Blvd Saratoga Way Turn Lanes, CIP 36105076

- **Description:** Construct left turn pocket extension and add right turn pocket ADA upgrade to the existing curb and gutter.
 - Total Project Cost: \$3,000,000.00
 - Funding Source: TIF Zone C
 - Project Start: August 2024
 - Estimated Project Completion: December 2024

Silva Valley/US 50 Interchange Phase 1A, CIP 71368

- **Description:** Landscape project necessary to complete mitigation requirements resulting from construction of the interchange.
 - Total Project Cost: \$1,914,845.00
 - Funding Source: TIM - Silva Valley Set Aside Zn 8
 - Project Start: November 2023
 - Estimated Project Completion: December 2029

Bass Lake Road and Bridlewood Roundabout

- **Description:** Construct a single-lane roundabout at the intersection of Bass Lake Road and Bridlewood Drive
 - Total Project Cost: \$4,198,000.00
 - Funding Source: CMAQ, RSTP Advance, and Bass Lake Bridlewood SRF
 - Project Start: November 2024
 - Estimated Project Completion: December 2033

Pedestrian Safety Improvements, CIP 36105073

- **Description:** Pedestrian safety improvements, including the installation of high visibility crosswalks and rectangular rapid flashing beacons.
 - Total Project Cost: \$600,000
 - Funding Source: Highway Safety Improvement Program Funds, Regional Surface Transportation Program Advance – Exchange Funds
 - Project Start: June 2024
 - Estimated Project Completion: September 2024

Harvard Way and Clermont Way Intersection Improvements, CIP 36105080

- **Description:** The project includes a traffic signal and partners with El Dorado Union High School District to improve Oak Ridge High School's campus traffic circulation plan for increased safety.
 - Total Project Cost: \$2,285,888
 - Funding Source: Traffic Impact Fees Zone C and Road Fund
 - Project Start: May 2024
 - Estimated Project Completion: August 2024

Countywide Projects:

Fire Hazard Mitigation Project, CIP 36106003

- **Description:** Mitigate wildfire risk by reducing hazardous fuels along targeted roadways throughout El Dorado County.
 - Total Project Cost: \$2,740,306
 - Funding Sources: FEMA – Fire Hazard Mitigation Grant Program, General Fund, and RSTP Advance Match
 - Project Start: October 2024
 - Estimated Project Completion: March 2025

Developer Projects:

Bell Ranch Units 1 & 2

- Description: Construct 114 homes and internal streets at Terra De Dios Dr. and Morrison Rd.
- Construction Status: Nearly Complete

Bass Lake North

- Description: Construct 90 homes and internal streets off Sienna Ridge and North Silver Dove
- Construction Status: Nearly Complete / 2024

Bass Lake North Bike Trail

- Description: Construct a bike trail from Hollow Oak Drive to Old Country Club Drive
- Construction Status: Spring 2024

Developer Projects Cont...

Hawk View

- Description: Punch-list and project closeout
- Construction Status: Nearly Complete

Folsom / EDH Self Storage

- Description: Frontage improvements along Green Valley Rd.
- Construction Status: Underway

Folsom Ranch

- Description: Emergency vehicle access road to the Folsom Ranch Subdivision.
- Construction Status: TBD

Promontory Village 7 Unit 1

- Description: Construct 28 homes, internal streets, and Sophia Parkway frontage
- Construction Status: Nearly Complete

Promontory Village 7 Unit 2

- Description: Construct 23 homes, internal streets
- Construction Status: Summer 2024

Promontory Village 7 Unit 3

- Description: Construct 44 homes, internal streets, and Beatty Dr. frontage
- Construction Status: Underway

Promontory Village 7 Unit 5

- Description: Construct 8 homes, internal streets, and Sophia Parkway frontage
- Construction Status: Underway

Ridgeview Unit 9

- Description: Construct 43 homes and road improvements
- Construction Status: Nearly Complete

Ridgeview West Unit 5

- Description: Construct 7 homes and driveways to Via Treviso / Via Barlogio
- Construction Status: Nearly complete

Serrano Village A14

- Description: Construct 51 homes and internal streets off Village Green Dr. and Russi Ranch Dr.
- Construction Status: 2025

Serrano Village C2

- Description: Construct 25 homes and internal streets
- Construction Status: 2025

Serrano Village M4

- Description: Construct 38 homes and internal streets off Raphael Dr. north of Mondrian Ct.
- Construction Status: Nearly Complete / 2024

Southpointe Meadows

- Description: Construct 7 homes and internal streets at Lakehills Dr. and Castec Wy.
- Construction Status: TBD